

TEST REPORT

Report No.: C9424.01-301-44

Rendered to:

ALL WEATHER ARCHITECTURAL ALUMINUM Vacaville, California

SERIES/MODEL: 5000 Series

PRODUCT TYPE: Thermally Broken Aluminum XOXX Casement Combination Window

SPECIFICATION: AAMA/WDMA/CSA 101/I.S.2/A440-08, NAFS - North American Fenestration Standard/Specification for Windows, Doors, and Skylights
AND

AAMA/WDMA/CSA 101/I.S.2/A440-05, Standard/Specification for Windows, Doors, and Unit Skylights.

Title	Summary of Results	
Primary Product Designator,	Class C – PG50: Size Tested 3251 x 1510	
AAMA/WDMA/CSA 101/I.S.2/A440-08	(128 x 60) – Type C	
Primary Product Designator,	C – C50 3251 x 1510 (128 x 60)	
AAMA/WDMA/CSA 101/I.S.2/A440-05	C = C30 323 x 1310 (128 x 00)	
Design Pressure	±2400 Pa (±50.13 psf)	
Air Infiltration	$<0.1 \text{ L/s/m}^2 (<0.01 \text{ cfm/ft}^2)$	
Water Penetration Resistance Test Pressure	360 Pa (7.52 psf)	

Test Completion Date: 06/21/2013

Reference must be made to Report No. C9424.01-301-44 dated 01/21/14 for complete test specimen description and detailed test results.



Test Report No.: C9424.01-301-44

Report Date: 01/21/14 Record Retention End Date: 06/21/17

Page 1 of 7

1.0 Report Issued To: All Weather Architectural Aluminum

777 Aldridge Road

Vacaville, California 95688

2.0 Test Laboratory: Architectural Testing, Inc.

2524 East Jensen Avenue Fresno, California 93706

559-233-8705

3.0 Project Summary:

3.1 Series/Model: 5000 Series

3.2 Product Type: Thermally Broken Aluminum

XOXX Casement Combination Window

3.3 Compliance Statement: Results obtained are tested values and were secured by using the designated test methods. The specimen tested successfully met the performance requirements for an AAMA/WDMA/CSA 101/I.S.2/A440-08 rating of Class C - PG50: Size Tested 3251 x 1510 (128 x 60) - Type C, and an AAMA/WDMA/CSA 101/I.S.2/A440-05 rating of C - C50 3251 x 1510 (128 x 60).

3.4 Test Dates: 06/17/2013 - 06/21/2013

3.5 Test Record Retention End Date: All test records for this report will be retained until June 21, 2017.

3.6 Test Location: Architectural Testing, Inc. test facility in Fresno, California.

3.7 Test Sample Source: The test specimen was provided by the client.

3.8 Drawing Reference: The test specimen drawings have been reviewed by Architectural Testing and are representative of the test specimen reported herein. Test specimen construction was verified by Architectural Testing per the drawings located in Appendix B. Any deviations are documented herein or on the drawings.

3.9 List of Official Observers:

<u>Name</u>	<u>Company</u>
Seamus Porter Jay Ratliff Jeff Osugi David Douglass	All Weather Architectural Aluminum Architectural Testing, Inc. Architectural Testing, Inc. Architectural Testing, Inc.
	The state of the s



Record Retention End Date: 06/21/17

Page 2 of 7

4.0 Test Specifications:

AAMA/WDMA/CSA 101/I.S.2/A440-08, NAFS - North American Fenestration Standard/Specification for Windows, Doors, and Skylights

AAMA/WDMA/CSA 101/I.S.2/A440-05, Standard/Specification for Windows, Doors, and Unit Skylights.

5.0 Test Specimen Description:

5.1 Product Sizes:

Overall Area:	Width		Hei	ght
4.92 m ² (52.9 ft ²)	millimeters	inches	millimeters	inches
Overall size	3251	128	1510	59-7/16
Panels (3)	807	31-3/4	1499	59

5.2 Frame Construction:

Frame Member	Material	Description
Head, Sill,	Aluminum	Extruded aluminum with poured and debridged
and Jambs	Aluminum	thermal break.
Mullions	Alumaimuma	Extruded aluminum with poured and debridged
Iviuilions	Aluminum	thermal break.

	Joinery Type	Detail
Frame corners	Mitered	Corners were welded; sealed with seam sealer.
Vertical Mullion joints	Coped	Mullion ends were coped and staked at tabs through slots in head and sill; sealed with seam sealer.

5.3 Panel Construction:

Member	Material	Description
Dails and stiles	Rails and stiles Aluminum	Extruded aluminum with poured and debridged
Rails allu stiles		thermal break.

	Joinery Type	Detail
All Panel Corners	Miter	Joined with aluminum corner keys crimped in place; sealed with seam sealer.



Record Retention End Date: 06/21/17

Page 3 of 7

5.0 Test Specimen Description: (Continued)

5.4 Weatherstripping:

Description	Quantity	Location
Hollow bulb vinyl	1 row	Active panel stiles and rails.
Hollow bulb vinyl	1 row	Frame at panel opening perimeter.

5.5 Glazing: No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method
1" IG	Aluminum	1/8" clear annealed	1/8" clear annealed	Glazing was set from the exterior onto 3/8" wide double-sided foam tape sealed at the corners with silicone; secured using a snap-fit glazing bead with a rubber gasket against the glass.

Location	Ougantity	Ouantity Daylight Opening		
Location	Quantity	millimeters	inches	Glass Bite
Panels	3	695 x 1386	27-3/8 x 54-9/16	5/8"
Fixed	1	752 x 1441	29-5/8 x 56-3/4	5/8"

5.6 Drainage:

Drainage Method	Size	Quantity	Location
Weep Notch	7/16" x 1/8"	2	Sill exterior leg at fixed lite, 7/8" from each corner.
Weep Notch	7/16" x 1/8"	6	Sill exterior leg at vent openings, 7/8" from each corner.
Weep Notch	7/16" x 1/8"	6	Bottom rail exterior glazing track leg, 7/8" from each corner.
Weatherstripping	1" Gap	6	Bottom rail, 1" from each corner.
Weatherstripping	1/4" Gap	6	Stiles, 1" from each top corner.



Test Report No.: C9424.01-301-44

Report Date: 01/21/14 Record Retention End Date: 06/21/17

Page 4 of 7

5.0 Test Specimen Description: (Continued)

5.7 Hardware:

Description	Quantity	Location
Locking handle assembly	6	14" from each end of lock stiles; each attached with two #10-24 x 5/8" Phillips flat head screws.
Strike plate	6	Opposite locks; each attached to vertical lock mullion with two #10-24 x 5/16" Phillips flat head screws.
Multi-arm hinge assembly	6	Attached using five #10 x 7/16" square-drive self-drilling pan head screws in the top and bottom rails, and four #10 x 5/8" square-drive self-drilling pan head screws in the frame.

5.8 Reinforcement: No reinforcement was utilized.

5.9 Screen Construction: No screen was utilized.

6.0 Installation:

The specimen was installed into a Douglas fir buck. The rough opening allowed for a 1/4" shim space. The exterior perimeter of the window was sealed with silicone.

Location	Anchor Description	Anchor Location	
Nail fin	1/4" x 2" Phillips flat head screw	1-1/2" from each corner and	
		spaced 8-1/2" - 13" on center.	



Record Retention End Date: 06/21/17

Page 5 of 7

7.0 Test Results: The temperature during testing was 21°C (69°F). The results are tabulated as follows:

Title of Test	Results	Allowed	Note
Operating Force,			
per ASTM E 2068			
<u>Initiate motion</u>	85 N (19.0 lbf)	Report Only	
Maintain motion	46 N (10.3 lbf)	100 N (22.5 lbf) max.	
<u>Locks</u>	20 N (4.5 lbf)	100 N (22.5 lbf) max.	
Air Leakage,			
Infiltration per ASTM E 283	<0.1 L/s/m ²	1.5 L/s/m ²	
at 75 Pa (1.57 psf)	(<0.01 cfm/ft ²)	(0.3 cfm/ft ²) max.	1
Water Penetration,			
per ASTM E 547	N/A	N/A	3
Uniform Load Deflection,			
per ASTM E 330	N/A	N/A	3
Uniform Load Structural,			
per ASTM E 330	N/A	N/A	3
Forced Entry Resistance, per			
ASTM F 588, Type B, Grade 10			
and per CAWM-301, Type II	Pass	No entry	
Sash Vertical Deflection Test			
270 N (60.7 lbf)	<0.1 mm (<0.01")	16.1 mm (0.64") max.	
Distributed Load Test			
300 psf (6.27 psf)	No damage	No damage	
C	ptional Performance		
Water Penetration,			
per ASTM E 547			
at 360 Pa (7.52 psf)	Pass	No leakage	2
Uniform Load Deflection,			
per ASTM E 330			
<u>Hinge Stile</u>			
-2520 Pa (-52.63 psf)	2.9 mm (0.12")	8.6 mm (0.34")	
+2520 Pa (+52.63 psf)	1.1 mm (0.05")	8.6 mm (0.34")	
Lock-to-Fixed Mullion			
-2520 Pa (-52.63 psf)	7.4 mm (0.29")	8.4 mm (0.33")	
+2520 Pa (+52.63 psf)	5.0 mm (0.20")	8.4 mm (0.33")	
Fixed-to-Hinge Mullion			
-2520 Pa (-52.63 psf)	5.1 mm (0.20")	8.4 mm (0.33")	
+2520 Pa (+52.63 psf)	5.0 mm (0.20")	8.4 mm (0.33")	
Lock-to-Lock Mullion			
-2520 Pa (-52.63 psf)	7.4 mm (0.29")	8.4 mm (0.33")	
+2520 Pa (+52.63 psf)	3.9 mm (0.16")	8.4 mm (0.33")	4, 5, 6



Record Retention End Date: 06/21/17

Page 6 of 7

7.0 Test Results: (Continued)

Title of Test	Results	Allowed	Note			
Optional Performance (Continued)						
Uniform Load Structural,						
per ASTM E 330						
<u>Hinge Stile</u>						
-3600 Pa (-75.19 psf)	0.1 mm (0.01")	4.5 mm (0.18")				
+3600 Pa (+75.19 psf)	0.0 mm (0.00")	4.5 mm (0.18")				
Lock-to-Fixed Mullion						
-3600 Pa (-75.19 psf)	0.0 mm (0.00")	4.4 mm (0.17")				
+3600 Pa (+75.19 psf)	0.3 mm (0.01")	4.4 mm (0.17")				
Fixed-to-Hinge Mullion						
-3600 Pa (-75.19 psf)	0.3 mm (0.01")	4.4 mm (0.17")				
+3600 Pa (+75.19 psf)	0.0 mm (0.00")	4.4 mm (0.17")				
Lock-to-Lock Mullion						
-3600 Pa (-75.19 psf)	0.6 mm (0.03")	4.4 mm (0.17")				
+3600 Pa (+75.19 psf)	0.0 mm (0.00")	4.4 mm (0.17")	5, 6			

Note 1: The tested specimen meets (or exceeds) the performance levels specified in AAMA/WDMA/CSA 101/I.S.2/A440 for air leakage resistance.

Note 2: Without insect screen.

Note 3: The client opted to start at a pressure higher than the minimum required. Test results are reported under Optional Performance.

Note 4: The allowable limits reported are the more restrictive according to either AAMA/WDMA/CSA 101/I.S.2/A440-05 or AAMA/WDMA/CSA 101/I.S.2/A440-08, for the respective product designations given. The data reported may also be used for special code compliance and informational purposes.

Note 5: Loads were held for 10 seconds.

Note 6: Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.



Test Report No.: C9424.01-301-44

Report Date: 01/21/14

Record Retention End Date: 06/21/17

Page 7 of 7

Architectural Testing will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by Architectural Testing, Inc. for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, Inc.

Digitally Signed by: David Douglass

David Douglass Project Manager Digitally Signed by:Leaton Kirk

eat Frie

Leaton Kirk Director – Regional Operations

DD: ms

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix-A: Alteration Addendum (1)

Appendix-B: Drawings (7)